

ADVERTISEMENT FOR BIDS/PUBLIC NOTICE TO BIDDERS

Sealed proposals will be received at the Purchasing Department, City of Mentor, 8500 Civic Center Boulevard, Mentor, Ohio until 10:00 AM on January 23, 2017 and will be opened and read immediately thereafter for the following roadway resurfacing project:

**2017 ROAD REPAIR PROGRAM
OPINION OF PROBABLE CONSTRUCTION COST:**

**CONTRACT A - \$920,500.00
ALTERNATE 1 - \$105,000.00
ALTERNATE 2 - \$93,000.00
COMPLETION DATE: 8/18/2017**

**CONTRACT B - \$281,500.00
ALTERNATE 1 - \$46,500.00
ALTERNATE 2 - \$87,500.00
ALTERNATE 3 - \$26,000.00
COMPLETION DATE: 8/18/2017**

Bids must be in accordance with specifications advertised on the City of Mentor website: www.cityofmentor.com/category/rfp or RFP's will be available for pick-up at the Purchasing Office.

BY ORDER OF

Kenneth J. Filipiak , City Manager

Publish: *News-Herald*

**PROPOSAL TO THE CITY OF MENTOR
For 2017 Pavement Repair Program - CONTRACT A - ALTERNATE 1 MOTL (Asphalt Pavement Planing, Resurfacing)**

REF. NO.	DESCRIPTION	QTY.	MEASURE UNITS	UNIT PRICE LABOR	UNIT PRICE MATERIAL	TOTAL UNIT PRICE	ITEM TOTAL
1	(253) PAVEMENT REPAIR, AS PER PLAN	190.00	SQ YD	\$	\$	\$	\$
2	(254) PAVEMENT PLANING, BITUMINOUS, AS PER PLAN	8,750.00	SQ YD	\$	\$	\$	\$
3	(407) TACK COAT, TRACKLESS, 702.13, AS PER PLAN	875.00	GALLON	\$	\$	\$	\$
4	(441) ASPHALT CONCRETE SURFACE COURSE, TYPE 1, (448), PG64-22	486.11	CU YD	\$	\$	\$	\$
5	(614) MAINTAINING TRAFFIC	1.00	LUMP	\$	\$	\$	\$
6	(SPC) BONDS AND INSURANCES, AS PER PLAN	1.00	LUMP	\$	\$	\$	\$
INFORMAL TOTAL BID \$							

**PROPOSAL TO THE CITY OF MENTOR
For 2017 Pavement Repair Program - CONTRACT A - ALTERNATE 2 (Asphalt Pavement Planing, Resurfacing)**

REF. NO.	DESCRIPTION	QTY.	MEASURE UNITS	UNIT PRICE LABOR	UNIT PRICE MATERIAL	TOTAL UNIT PRICE	ITEM TOTAL
1	(253) PAVEMENT REPAIR, AS PER PLAN	450.00	SQ YD	\$	\$	\$	\$
2	(254) PAVEMENT PLANING, BITUMINOUS, AS PER PLAN	8,950.00	SQ YD	\$	\$	\$	\$
3	(407) TACK COAT, TRACKLESS, 702.13, AS PER PLAN	895.00	GALLON	\$	\$	\$	\$
4	(441) ASPHALT CONCRETE SURFACE COURSE, TYPE 1, (448), PG64-22	372.92	CU YD	\$	\$	\$	\$
INFORMAL TOTAL BID \$							

BF.11A

QUANTITY WORKSHEET

For 2017 Pavement Repair Program - CONTRACT A (1 1/2" Pavement Planing/3" Asphalt Resurfacing(LaFayette); 2" planing/resurfacing (Adkins); 1.5" planing/resurfacing (all other streets))

REF. NO.	DESCRIPTION	ESTIMATED TOTAL QTY.	MEASURE UNITS	LAFAYETTE	ADKINS	HOPKINS	MENTOR PARK	ELMWOOD	SPRING VALLEY	ROSELAWN	DANBURY	ANACONDA	GROVE	HARBOR	HILLCREST	PINECONE	PINENEEDLE
				FAIRFAX TO FINDLEY	REYNOLDS TO WEST CORP	MENTOR AVE TO SR 84	EMERY TO ELMWOOD	BELLFLOWER TO HOWELL	JACKSON TO EAST	KING MEMORIAL TO FAIRLAWN	CUMBERLAND TO CONCRETE	LAKE SHORE TO RUSHTON	LAKE SHORE TO RUSHTON	LAKE SHORE TO BRIDGE	LAKE SHORE TO HOPKINS	HESLEY TO NORTH	HESLEY TO PINECONE
1	(253) PAVEMENT REPAIR, AS PER PLAN	4,550.00	SQ YD			1,750											
2	(251) 3 INCH PARTIAL DEPTH PAVEMENT REPAIR, AS PER PLAN	2,300.00	SQ YD	1,620													
3	(254) PAVEMENT PLANING, BITUMINOUS, AS PER PLAN	56,735.00	SQ YD		9,605		15,025	7,185	5,210	2,885	480	3,195	2,730	7,550	2,860	340	340
4	(254) PAVEMENT PLANING, PORTLAND CEMENT CONCRETE, AS PER PLAN	1,020.00	SQ YD	1,020.0													
5	(407) TACK COAT, TRACKLESS, 702.13	5,883.50	GALLON		950.5		1,502.5	718.5	521.0	288.5	49.0	319.5	273.0	755.0	285.0		
6	(407) TACK COAT, TRACKLESS, FOR INTERMEDIATE COURSE	105.00	GALLON	105.0													
7	(448) ASPHALT CONCRETE INTERMEDIATE COURSE, TYPE 1, PG64-22	87.50	CU YD	87.50													
8	(448) ASPHALT CONCRETE SURFACE COURSE, TYPE 1, PG70-22M	87.50	CU YD	87.50													
9	(448) ASPHALT CONCRETE SURFACE COURSE, TYPE 1, PG64-22	2,467.36	CU YD		533.61		826.04	299.38	217.08	120.21	20.42	133.13	113.75	314.58	119.17		
10	(SPEC) HYBRID INTERLAYER PAVING MAT, GLASPAVE 25, AS PER PLAN	2,100.00	SQ YD	2,100.00													
11	(804) MANHOLE/INLET BASIN RECONSTRUCTED TO GRADE	6.00	EACH	6													
12	(804) MONUMENT BOX ADJUSTED TO GRADE, AS PER PLAN	6.00	EACH	6													
13	(642) CROSSWALK LINE	94.00	L.F.											94			
14	(642) STOP LINE	133.00	L.F.				45			14		11	11	22	30		
15	(642) CENTER LINE	1.66	MILE		0.85		1.01										
16	(642) EDGE LINE	3.33	MILE		1.3		2.03										
17	(SPC) BONDS AND INSURANCES, AS PER PLAN		LUMP														
18	(SPC) PRE-CONSTRUCTION VIDEO, AS PER PLAN		LUMP														
19	(614) MAINTAINING TRAFFIC		LUMP														
20	(624) MOBILIZATION		LUMP														
21	CONTINGENCY		LUMP														

QUANTITY WORKSHEET

For 2017 Pavement Repair Program - CONTRACT A - ALTERNATE 1 MOTL (2" mill/fill)

REF. NO.	DESCRIPTION	ESTIMATED TOTAL QTY.	MEASURE UNITS	PRIMROSE	DAHLIA	HICKORY	WEDGEWOOD	CEDARWOOD
				LAKE TO REYNOLDS	LAKE TO REYNOLDS	LINDEN TO LAKE SHORE	EAST LAURA TO CORP LIMITS	MAPLEWOOD TO FIRWOOD
1	(253) PAVEMENT REPAIR, AS PER PLAN	190.00	SQ YD					
2	(254) PAVEMENT PLANING, BITUMINOUS, AS PER PLAN	8,750.00	SQ YD	1,955	1,985	2,338	1,312	1,172
3	(407) TACK COAT, TRACKLESS, 702.13	875.00	GALLON	196.6	196.5	233.6	131.2	117.2
4	(441) ASPHALT CONCRETE SURFACE COURSE, TYPE 1, (448), PG64-22	486.11	CU YD	108.17	106.17	129.78	72.89	65.11
5	(614) MAINTAINING TRAFFIC		LUMP					
6	(SPC) BONDS AND INSURANCES, AS PER PLAN		LUMP					

QUANTITY WORKSHEET

For 2017 Pavement Repair Program - CONTRACT A - ALTERNATE 2 (1.5" mill/fill)

REF. NO.	DESCRIPTION	ESTIMATED TOTAL QTY.	MEASURE UNITS	FAIRLAWN	PINE TREE	WASATKA	DEERBORN
				SR 84 TO CHILLICOTHE	BELLFLOWER TO EDGEWOOD	IROQUOIS TO SENECA	LAKE SHORE TO RUSHTON
1	(253) PAVEMENT REPAIR, AS PER PLAN	450.00	SQ YD				
2	(254) PAVEMENT PLANING, BITUMINOUS, AS PER PLAN	8,950.00	SQ YD	2,885	2,285	850	2,930
3	(407) TACK COAT, TRACKLESS, 702.13	896.00	GALLON	288.5	228.5	85.0	293.0
4	(441) ASPHALT CONCRETE SURFACE COURSE, TYPE 1, (448), PG64-22	372.92	CU YD	120.21	95.21	35.42	122.08

QUANTITY WORKSHEET

For 2016 Pavement Repair Program - CONTRACT B (CONCRETE PAVEMENT REPAIRS - Estimated 6" TO 9" thickness)

REF. NO.	DESCRIPTION	ESTIMATED TOTAL QUANTITY	MEASURE UNITS	INDUSTRIAL PARK, JUSTIN WAY		DEER RIDGE, GROVEWOOD, FARLEY, JODY LYNN	
1	(255) FULL DEPTH PAVEMENT REMOVAL AND RIGID REPLACEMENT, CLASS QC MS, AS PER PLAN	3,350.00	SQ YD		2,350		1,000
2	(SPC) BONDS AND INSURANCES, AS PER PLAN	1	LUMP				
3	(614) MAINTAINING TRAFFIC	1	LUMP				
4	CONTINGENCY	1	LUMP				

QUANTITY WORKSHEET

For 2017 Pavement Repair Program - CONTRACT B - ALTERNATE 1 MOTL (CONCRETE PAVEMENT REPAIRS - Estimated 6" TO 9" thickness)

REF. NO.	DESCRIPTION	ESTIMATED TOTAL QUANTITY	MEASURE UNITS	VARIOUS LOCATIONS (SEE NEXT SHEET)	
1	(255) FULL DEPTH PAVEMENT REMOVAL AND RIGID REPLACEMENT, CLASS QC MS, AS PER PLAN	370.00	SQ YD		370.5
2	(804) MANHOLE/INLET BASIN RECONSTRUCTED TO GRADE (AS PER PLAN)	13.00	EACH		13
3	(SPC) BONDS AND INSURANCES, AS PER PLAN	1	LUMP		
4	(614) MAINTAINING TRAFFIC	1	LUMP		

QUANTITY WORKSHEET

For 2017 Pavement Repair Program - CONTRACT B - ALTERNATE 2 (CONCRETE PAVEMENT REPAIRS - Estimated 6" TO 9" thickness)

REF. NO.	DESCRIPTION	ESTIMATED TOTAL QUANTITY	MEASURE UNITS	VARIOUS LOCATIONS, (AS DIRECTED)	
1	(255) FULL DEPTH PAVEMENT REMOVAL AND RIGID REPLACEMENT, CLASS QC MS, AS PER PLAN	1,250.00	SQ YD		1,250

QUANTITY WORKSHEET

For 2017 Pavement Repair Program - CONTRACT B - ALTERNATE 3 (CONCRETE PAVEMENT REPAIRS - Estimated 6" TO 9" thickness)

REF. NO.	DESCRIPTION	ESTIMATED TOTAL QUANTITY	MEASURE UNITS	VARIOUS LOCATIONS, (AS DIRECTED)	
1	(804) MANHOLE/INLET BASIN RECONSTRUCTED TO GRADE (AS PER PLAN)	21.00	EACH		21