

ADDENDUM 1

March 2, 2026

To All Bidders:

This Addendum alters and amends:

1. The original bid form.
2. Includes the addition of an estimated road quantities sheet.

You must indicate receipt of Addendum 1, on your BF.11 (Signature Page) Form.

END OF ADDENDUM 1

PROPOSAL TO THE CITY OF MENTOR

2026 Asphalt Road Repair Program - (Asphalt Pavement Planing, Resurfacing)

REF. NO.	DESCRIPTION	QTY.	MEASURE UNITS	UNIT PRICE	UNIT PRICE	TOTAL UNIT PRICE	ITEM TOTAL
				LABOR	MATERIAL	PRICE	
1	(253) PAVEMENT REPAIR 4 INCH, AS PER PLAN	6,300.00	SY	\$	\$	\$	\$
2	(253) PAVEMENT REPAIR 7 INCH, AS PER PLAN	1,500.00	SY	\$	\$	\$	\$
3	(254) PAVEMENT PLANING, BITUMINOUS (1.5")	64,500.00	SY	\$	\$	\$	\$
4	MISC. PAVEMENT REPAIR (7" MILL, 5.5" 301 BASE, 1.5" SURFACE)	225.00	SY	\$	\$	\$	\$
5	(407) TACK COAT, TRACKLESS, 702.13	6,450.00	GALLON	\$	\$	\$	\$
6	(441) ASPHALT CONCRETE SURFACE COURSE, TYPE 1, (448), PG70-22M	2,688.00	CY	\$	\$	\$	\$
7	(611) MANHOLE OR INLET BASIN ADJUSTED TO GRADE	25.00	EACH	\$	\$	\$	\$
8	(611) MANHOLE OR INLET BASIN RECONSTRUCTED TO GRADE	3.00	EACH	\$	\$	\$	\$
9	(638) GAS AND WATER AND MONUMENT BOX ADJUSTED TO GRADE	7.00	EACH	\$	\$	\$	\$
10	(609) REMOVE AND REPLACE CONCRETE CURB OR CURB AND GUTTER, AS DIRECTED	1,000.00	LF	\$	\$	\$	\$
11	(614) MAINTAINING TRAFFIC	1.00	LUMP	\$	\$	\$	\$
12	(614) WORK ZONE CENTER LINE, CLASS 1	1.00	LUMP	\$	\$	\$	\$
13	(642) PAVEMENT MARKINGS PER PLAN	1.00	LUMP	\$	\$	\$	\$
14	CONTINGENCY	1.00	LUMP	XXXXXXXXXX	XXXXXXXXXX	\$50,000.00	\$50,000.00
						BASE BID TOTAL \$	

Alternate 1-Mentor on the Lake

REF. NO.	DESCRIPTION	QTY.	MEASURE UNITS	UNIT PRICE	UNIT PRICE	TOTAL UNIT PRICE	ITEM TOTAL
				LABOR	MATERIAL	PRICE	
1	(209) LINEAR GRADING	0.42	MILE	\$	\$	\$	\$
2	(251) PAVEMENT REPAIR, AS PER PLAN (7 INCH)	257.00	SY	\$	\$	\$	\$
3	(407) TACK COAT, TRACKLESS, 702.13, AS PER PLAN	384.00	GALLON	\$	\$	\$	\$
4	(441) ASPHALT CONCRETE SURFACE COURSE, TYPE 1, (448), PG64-22, T=1.25 INCH	96.00	CY	\$	\$	\$	\$
5	(441) ASPHALT CONCRETE INTERMEDIATE COURSE COURSE, TYPE 2, (448), PG64-22, T=1.75 INCH	134.00	CY	\$	\$	\$	\$
6	(897) PAVEMENT PLANNING, ASPHALT CONCRETE, CLASS A - FINE PLANNING, T=3 INCH	2,723.00	SY	\$	\$	\$	\$
7	(SPECIAL) HYBRID INTERLAYER PAVING MAT, MPM 30	2,574.00	SY	\$	\$	\$	\$
						ALTERNATE 1 TOTAL \$	

Alternate 2 - Dawson Boulevard

REF. NO.	DESCRIPTION	QTY.		UNIT	UNIT	TOTAL	
			MEASURE	PRICE	PRICE	UNIT	ITEM
			UNITS	LABOR	MATERIAL	PRICE	TOTAL
1	(253) PAVEMENT REPAIR, AS PER PLAN (4 INCH)	628.00	SY	\$	\$	\$	\$
2	(254) PAVEMENT PLANING, BITUMINOUS (1.5")	6,277.00	SY	\$	\$	\$	\$
3	(611) MANHOLE OR INLET BASIN ADJUSTED TO GRADE	2.00	EACH	\$	\$	\$	\$
4	(407) TACK COAT, TRACKLESS, 702.13	628.00	GALLON	\$	\$	\$	\$
5	(441) ASPHALT CONCRETE SURFACE COURSE, TYPE 1, (448), PG70-22M	262.00	CY	\$	\$	\$	\$
						ALTERNATE 2 TOTAL \$	

Alternate 3 - Ivy Court

REF. NO.	DESCRIPTION	QTY.		UNIT	UNIT	TOTAL	
			MEASURE	PRICE	PRICE	UNIT	ITEM
			UNITS	LABOR	MATERIAL	PRICE	TOTAL
1	(253) PAVEMENT REPAIR, AS PER PLAN (4 INCH)	113.00	SY	\$	\$	\$	\$
2	(254) PAVEMENT PLANING, BITUMINOUS (1.5")	1,134.00	SY	\$	\$	\$	\$
3	(611) MANHOLE OR INLET BASIN ADJUSTED TO GRADE	2.00	EACH	\$	\$	\$	\$
4	(638) GAS AND WATER AND MONUMENT BOX ADJUSTED TO GRADE	3.00	EACH	\$	\$	\$	\$
5	(407) TACK COAT, TRACKLESS, 702.13	113.00	GALLON	\$	\$	\$	\$
6	(441) ASPHALT CONCRETE SURFACE COURSE, TYPE 1, (448), PG70-22M	47.00	CY	\$	\$	\$	\$
						ALTERNATE 3 TOTAL \$	

Alternate 4 - Wheeler Court

REF. NO.	DESCRIPTION	QTY.		UNIT	UNIT	TOTAL	
			MEASURE	PRICE	PRICE	UNIT	ITEM
			UNITS	LABOR	MATERIAL	PRICE	TOTAL
1	(253) PAVEMENT REPAIR, AS PER PLAN (4 INCH)	188.00	SY				
2	(254) PAVEMENT PLANING, BITUMINOUS (1.5")	1,882.00	SY				
3	(407) TACK COAT, TRACKLESS, 702.13	188.00	GALLON				
4	(441) ASPHALT CONCRETE SURFACE COURSE, TYPE 1, (448), PG70-22M	78.00	CY				
						ALTERNATE 4 TOTAL \$	
						BASE BID PLUS ALTERNATES 1, 2, 3, AND 4 TOTAL	

2026 Road Repair Program - EST ROAD QUANTITIES

ASPHALT STREETS

	Asphalt Streets	WARD	DESCRIPTION	AREA (SY)	TREATMENT
1	Perkins	1	Little Mountain to Low Ridge	6,489	MILL/FILL
2	Carole	2	Sharonlee to Lauren J	4,148	MILL/FILL
3	Welland	2	306 to Culver	6,335	MILL/FILL
4	Sylvia	2	Jackson to Burrige	2,335	MILL/FILL
5	Stamford	2	Dartmoor to church	3,990	MILL/FILL
6	Argee	2	Maple to Nowlen	2,816	MILL/FILL
7	Westmoor	2	Midland to 84	5,648	MILL/FILL
8	Brentwood	2	Rt 20 to 84	6,924	MILL/FILL
9	Comanche	3	Willoughby to east	1,596	MILL/FILL
10	Longhorn	3	Texas to Hawk	200	Spot Repair
11	Hawk	3	Longhorn to 306	5,364	MILL/FILL
12	Eric	3	Campbell to Reynolds	1,707	MILL/FILL
13	Ohio	3	306 to concrete	8,251	MILL/FILL
14	Blackbrook	4	Heisley to East corp limit	2,775	MILL/FILL
15	Willowbrook	4	Jordan to North	2,493	MILL/FILL
16	Dorrwood	4	Hilltop to Concrete	3,022	MILL/FILL

ALTERNATE STREETS

	Alternates		DESCRIPTION	AREA (SY)	TREATMENT
2	Dawson	3	Lakeshore to concrete	6,277	MILL/FILL
3	Ivy	3	Seminole to Cedarwood	1,134	MILL/FILL
4	Wheeler	4	French to Cul de sac	1,882	MILL/FILL