



DENK ASSOCIATES
CONSULTING ENGINEERS

503 EAST 200th STREET
CLEVELAND, OHIO 44119
PHONE: 216-531-8880
EMAIL: info@denkassoc.com

MENTOR SENIOR CENTER HVAC SYSTEM RENOVATION

Addendum #1 – 10/20/26

This Addendum becomes fully a part of the previously issued Quote Package as if originally issued therewith or originally contained therein.

The Addendum includes additions to, deductions from, changes and substitutions in, or clarifications and emphasis on parts or requirements of the drawings and specifications pertaining to the project.

Contractors shall familiarize themselves with Addendum items and they shall be held responsible for complete knowledge of same.

M601 MECHANICAL SCHEDULES, LEGENDS AND DETAILS

VAV BOXES WITH REHEAT (VAV-A thru VAV-F)

The terminal boxes shall be provided with the following:

- Hot Water Coil
- ½" Fiberglass Liner
- Averaging Air Flow Sensor
- Field Mounted Controls
- Coil Access Door
- Eco Low Leakage Series
- Hot Water Heat Water Coil
- Door, Coil Access- Zip Screw, Mounted On Bottom
- 22 Ga Construction
- Brackets- Hanger Brackets
- Slip and Drive Connection
- Z' Bracket On Discharge
- 1/2" Foil Faced 1 1/2 lbs.
- Center Averaging Flow Sensor
- No Control Field Supplied/Mounted
- Base Unit with No Controls
- Enclosure & Mounting Plate, Std Control Panel Enclosure and Std. Mntg Plate
- Disconnect and 24 VAC transformer

VAV BOXES WITH REHEAT (VAV-1 thru VAV-6)

The terminal boxes shall be provided with the following:

- Hot Water Coil
- ½" Fiberglass Liner
- Averaging Air Flow Sensor

Field Mounted Controls
Coil Access Door
Eco Low Leakage Series
Hot Water Heat Water Coil
Door, Coil Access- Zip Screw, Mounted On Bottom
22 Ga Construction
Brackets- Hanger Brackets
Slip and Drive Connection
Z' Bracket On Discharge
1/2" Foil Faced 1 1/2 lbs.
Center Averaging Flow Sensor
No Control Field Supplied/Mounted
Base Unit with No Controls
Enclosure & Mounting Plate, Std Control Panel Enclosure and Std. Mntg Plate
Disconnect and 24 VAC transformer

END OF ADDENDUM NO. 1