

# CITY OF MENTOR SWP3 GENERAL NOTES

**GENERAL EROSION AND SEDIMENT CONTROL NOTES**

EROSION CONTROL SHALL CONSIST OF TEMPORARY CONTROL MEASURES AS DETAILED ON THE PLANS OR ORDERED BY THE CITY OF MENTOR DURING THE TERM OF CONSTRUCTION TO CONTROL SOIL EROSION AND SEDIMENTATION THROUGH THE USE OF EROSION CONTROL BEST MANAGEMENT PRACTICES (BMP'S).

TEMPORARY EROSION AND SEDIMENT CONTROL ITEMS, THE LOCATION AND SIZE OF WHICH ARE DETAILED ON THE PLANS, SHALL BE INSTALLED BY THE CONTRACTOR PRIOR TO THE COMMENCEMENT OF ANY CLEARING OR EARTHWORK OPERATIONS. CONDITIONS THAT DEVELOP DURING CONSTRUCTION THAT WERE NOT FORSEEN DURING DESIGN STAGE, THAT REQUIRE ADDITIONAL OR MODIFIED TEMPORARY OR PERMANENT BMP'S SHALL BE APPROVED BY THE CITY ENGINEER AND REFLECTED ON THE REVISED SWP3.

SEDIMENT PONDS, SEDIMENT TRAPS, AND PERIMETER SEDIMENT CONTROLS, SHALL BE IMPLEMENTED PRIOR TO GRADING AND WITHIN 7 DAYS FROM THE START OF GRUBBING. THEY SHALL CONTINUE TO FUNCTION UNTIL THE UP SLOPE DEVELOPMENT AREAS ARE RE-ESTABLISHED WITH VEGETATION. SEDIMENT CONTROLS SHALL NOT BE PLACED IN A STREAM.

TRENCH DEWATERING OR GROUND WATER, WHICH CONTAINS SEDIMENT SHALL PASS THROUGH A SEDIMENT SETTLING POND OR EQUALLY EFFECTIVE SEDIMENT CONTROL DEVICE. ALTERNATIVES MAY INCLUDE DEWATERING INTO A SUMP PIT, FILTER BAG, OR EXISTING VEGETATED UPSLOPE AREA. SEDIMENT LADEN WATER SHALL NOT BE DISCHARGED TO STREAMS, WATER RESOURCES, OR THE STORM SEWER SYSTEM.

THE SWP3, NOTES AND DETAILED DRAWINGS ARE INTENDED TO SERVE AS BASIC GUIDELINES. ALL EROSION AND SEDIMENT CONTROL PRACTICES SHALL MEET THE STANDARDS AND SPECIFICATIONS OF THE OHIO DEPARTMENT OF NATURAL RESOURCES (ODNR) RAINWATER AND LAND DEVELOPMENT MANUAL.

ADDITIONAL EROSION AND SEDIMENT CONTROL BMP'S MAY BE REQUIRED BY THE CITY OF MENTOR AS UNFORSEEN SITUATIONS MAY ARISE THAT REQUIRE ADDITIONAL EROSION AND SEDIMENT CONTROL PRACTICES.

**CLEARING AND GRUBBING**

LIMITS OF CLEARING AND GRADING SHALL BE CLEARLY MARKED ON THE SITE WITH SIGNAGE, FLAGGING AND/OR ORANGE CONSTRUCTION FENCING.

THE CONTRACTOR SHALL LIMIT THE SURFACE AREA OF ERODIBLE EARTH MATERIAL EXPOSED BY EXCAVATION, BORROW AND FILL OPERATIONS AND PROVIDE IMMEDIATE PERMANENT OR TEMPORARY CONTROL MEASURES TO PREVENT CONTAMINATION OF ADJACENT STREAMS, WATER RESOURCES, WETLANDS, OR OTHER AREAS OF WATER IMPOUNDMENT.

**CONSTRUCTION ENTRANCE**

A STONED CONSTRUCTION ENTRANCE SHALL BE INSTALLED FOR ALL INGRESS AND EGRESS TO THE SITE. THE MINIMUM DIMENSIONS OF THE DRIVE SHALL BE 14 FEET WIDE BY 70 FEET LONG. THE STONE SHALL BE 6 INCHES DEEP WITH AN UNDERLAIN GEOTEXTILE FABRIC. THE DRIVE SHALL BE INSTALLED PRIOR TO ANY CLEARING AND GRUBBING. SEDIMENTS SHALL BE REMOVED FROM THE ROADWAY DAILY OR MORE FREQUENTLY IF REQUIRED BY THE CITY OF MENTOR.

**STABILIZATION**

PERMANENT AND TEMPORARY STABILIZATION SHALL OCCUR AS REQUIRED IN THE FOLLOWING TABLES:

TABLE 1: PERMANENT STABILIZATION

PERMANENT STABILIZATION	
AREA REQUIRING PERMANENT STABILIZATION	TIME FRAME TO APPLY EROSION CONTROL
ANY AREA THAT WILL LIE DORMANT FOR ONE YEAR OR MORE	WITHIN SEVEN DAYS OF THE MOST RECENT DISTURBANCE
ANY AREA WITHIN 50 FT. OF A SURFACE WATER OF THE STATE AND AT FINAL GRADE	WITHIN 2 DAYS OF REACHING FINAL GRADE
ANY OTHER AREAS AT FINAL GRADE	WITHIN 7 DAYS OF REACHING FINAL GRADE WITHIN THAT AREA

**TEMPORARY SEEDING**

SEEDED AREAS SHALL BE INSPECTED AND WHERE THE SEED HAS NOT PRODUCED 70% COVER SHALL BE RESEED BY THE CONTRACTOR. AREAS SHALL BE STABILIZED WITH STRAW MULCH WHEN CONDITIONS PROHIBIT SEEDING.

STRAW MULCH SHALL BE APPLIED AT A RATE OF 2-3 STANDARD 45 LB. BALES PER 1000 SQ. FT. OF DISTURBED AREA OR 2 TONS PER ACRE. ALL HYDROSEEDING MUST BE STRAW MULCHED ACCORDING TO THE ABOVE SPECIFICATIONS UNLESS IT IS WATERED WEEKLY.

ALL DETENTION PONDS, RETENTION PONDS, WATER QUALITY STRUCTURES, SEDIMENT PONDS, SEDIMENT TRAPS, EARTHEN DIVERSIONS, OR EMBANKMENTS SHALL BE SEEDED AND STRAW MULCHED WITHIN 7 DAYS OF COMPLETED CONSTRUCTION.

TABLE 2: TEMPORARY STABILIZATION

TEMPORARY STABILIZATION	
AREA REQUIRING PERMANENT STABILIZATION	TIME FRAME TO APPLY EROSION CONTROL
ANY DISTURBED AREAS WITHIN 50 FEET OF A SURFACE WATER OF THE STATE AND NOT AT FINAL GRADE	WITHIN 2 DAYS OF THE MOST RECENT DISTURBANCE IF THE AREA WILL REMAIN IDLE FOR MORE THAN 14 DAYS
FOR ALL CONSTRUCTION ACTIVITIES, ANY DISTURBED AREA, INCLUDING SOIL STOCKPILES THAT WILL BE DORMANT FOR MORE THAN 14 DAYS BUT LESS THAN 1 YEAR, AND NOT WITHIN 50 FEET OF A SURFACE WATER OF THE STATE	WITHIN 7 DAYS OF THE MOST RECENT DISTURBANCE WITHIN THE AREA
DISTURBED AREAS THAT WILL REMAIN IDLE OVER WINTER	PRIOR TO THE ONSET OF WINTER WEATHER (NOV. 1) STRAW MULCH 2-3 BALES PER 1000 SQ. FT. OR 2 TONS PER ACRE
NOTE: WHERE VEGETATIVE STABILIZATION TECHNIQUES ARE UNOBTAINABLE DUE TO INSTABILITY, EROSION MATTING MAY BE USED.	

**PERMANENT STABILIZATION OF CONVEYANCE CHANNELS**

THE CONTRACTOR SHALL UNDERTAKE SPECIAL MEASURES TO STABILIZE CHANNELS AND OUTFALLS AND PREVENT EROSION FLOWS. MEASURES MAY INCLUDE SEEDING, DORMANT SEEDING, MULCHING, EROSION CONTROL MATTING, SODDING, RIPRAP, NATURAL CHANNEL DESIGN WITH BIO-ENGINEERING TECHNIQUES, OR ROCK CHECK DAMS, ALL AS DEFINED IN THE MOST RECENT EDITION OF THE RAINWATER AND LAND DEVELOPMENT MANUAL PUBLISHED BY ODNR.

**SOIL TRANSPORT ONTO PUBLIC ROADS**

WHERE SOIL IS TRANSPORTED ONTO PUBLIC ROAD SURFACES, THE ROADS SHALL BE CLEANED THOROUGHLY BY EITHER SWEEPING OR SCRAPING AT THE END OF EACH WORK DAY OR MORE FREQUENTLY IF NEEDED IN ORDER TO ENSURE PUBLIC SAFETY. STREET WASHING IS NOT PERMITTED. IF APPLICABLE, THE CATCH BASINS NEAREST TO THE CONSTRUCTION ENTRANCE SHALL BE CLEANED WEEKLY.

ADDITIONAL REQUIREMENTS TO CONTROL SOIL TRANSPORT ONTO PUBLIC ROADS MAY INCLUDE:

- SILT FENCE OR CONSTRUCTION FENCE INSTALLED AROUND THE PERIMETER OF THE DEVELOPMENT AREA TO ENSURE ALL VEHICLE TRAFFIC ADHERES TO DESIGNATED CONSTRUCTION ENTRANCES.
- DESIGNATED WHEEL WASHING AREAS. WASH WATER FROM THESE AREAS MUST BE DIRECTED TO A DESIGNATED SEDIMENT TRAP, SEDIMENT SETTLING POND, OR TO A DEWATERING SUMP PIT.

ERODIBLE MATERIAL RAMPS IN STREETS TO ENABLE EQUIPMENT TO CROSS CURBS SHALL BE PROPERLY REMOVED IMMEDIATELY AFTER USE.

**SILT FENCE AND DIVERSIONS**

SHEET FLOW RUNOFF FROM DENUDED AREAS SHALL BE INTERCEPTED BY SILT FENCE OR DIVERSIONS TO PROTECT ADJACENT PROPERTIES, WATER RESOURCES, AND WETLANDS FROM SEDIMENT TRANSPORTED VIA SHEET FLOW. WHERE INTENDED TO PROVIDE SEDIMENT CONTROL, SILT FENCE SHALL BE PLACED ON A LEVEL CONTOUR AND SHALL BE CAPABLE OF TEMPORARILY PONDING RUNOFF. THE EPA PERMIT No. OHC000004 DOES NOT PRECLUDE THE USE OF OTHER SEDIMENT BARRIERS DESIGNED TO CONTROL SHEET FLOW RUNOFF.

STORM WATER DIVERSION PRACTICES SHALL BE USED TO KEEP RUNOFF AWAY FROM DISTURBED AREAS AND STEEP SLOPES. SUCH DEVICES, WHICH INCLUDE SWALES, DIKES OR BERMS, MAY RECEIVE STORM WATER RUNOFF FROM AREAS UP TO 10 ACRES.

**INLET PROTECTION**

INLET PROTECTION IS MANDATORY. INLET PROTECTION SHALL CONFORM TO THE REQUIREMENTS OF THE MOST RECENT VERSION OF THE RAINWATER AND LAND DEVELOPMENT MANUAL BY ODNR. ALL INLETS RECEIVING RUNOFF FROM DRAINAGE AREAS OF ONE OR MORE ACRES WILL REQUIRE A SEDIMENT SETTLING POND. STRAW OR HAY BALES ARE NOT ACCEPTABLE FORMS OF INLET PROTECTION.

**NON-SEDIMENT POLLUTANTS CONTROLS**

NO SOLID OR LIQUID WASTE, INCLUDING BUILDING MATERIALS, SHALL BE DISCHARGED IN STORM WATER RUNOFF. ALL NECESSARY BMP'S MUST BE IMPLEMENTED TO PREVENT THE DISCHARGE OF NON-SEDIMENT POLLUTANTS TO THE DRAINAGE SYSTEM OF THE SITE, WATER RESOURCES, OR WETLANDS. UNDER NO CIRCUMSTANCE SHALL CONCRETE TRUCKS WASH OUT DIRECTLY INTO A DRAINAGE CHANNEL, STREET, STORM SEWER, OR OTHER PUBLIC FACILITY OR NATURAL RESOURCE. EXPOSURE OF WASTE MATERIALS TO STORM WATER IS NOT RECOMMENDED.

**TRENCH AND GROUNDWATER CONTROL**

THERE SHALL BE NO SEDIMENT LADEN OR TURBID DISCHARGES TO WATER RESOURCES OR WETLANDS RESULTING FROM DEWATERING ACTIVITIES. IF TRENCH OR GROUND WATER CONTAINS SEDIMENT, IT MUST PASS THROUGH A SEDIMENT SETTLING POND OR OTHER EQUALLY EFFECTIVE SEDIMENT CONTROL DEVICE PRIOR TO BEING DISCHARGED FROM THE CONSTRUCTION SITE. ALTERNATIVELY, SEDIMENT MAY BE REMOVED BY SETTLING IN PLACE OR BY DEWATERING INTO A SUMP PIT, FILTER BAG, OR COMPARABLE PRACTICE. GROUND WATER DEWATERING WHICH DOES NOT CONTAIN SEDIMENT OR OTHER POLLUTANTS IS NOT REQUIRED TO BE TREATED PRIOR TO DISCHARGE. HOWEVER, CARE MUST BE TAKEN WHEN DISCHARGING GROUND WATER TO ENSURE THAT IT DOES NOT BECOME POLLUTANT LADEN BY TRAVERSING OVER DISTURBED SOILS OR OTHER POLLUTANT SOURCES.

**INSPECTION**

ALL CONTROLS ON THE SITE SHALL BE INSPECTED AT LEAST ONCE EVERY SEVEN CALENDAR DAYS AND WITHIN 24 HOURS AFTER ANY STORM EVENT GREATER THAN ONE-HALF INCH OF RAIN PER 24 HOUR PERIOD. THE CONTRACTOR SHALL ASSIGN QUALIFIED INSPECTION PERSONNEL TO CONDUCT THESE INSPECTIONS TO ENSURE THAT THE CONTROL PRACTICES ARE FUNCTIONAL AND TO EVALUATE WHETHER THE SWP3 IS ADEQUATE, OR WHETHER ADDITIONAL CONTROL MEASURES ARE REQUIRED. QUALIFIED INSPECTION PERSONNEL ARE INDIVIDUALS WITH KNOWLEDGE AND EXPERIENCE IN THE INSTALLATION AND MAINTENANCE OF SEDIMENT AND EROSION CONTROLS.

INSPECTIONS SHALL MEET THE FOLLOWING REQUIREMENTS:

- DISTURBED AREAS AND AREAS USED FOR STORAGE OF MATERIALS THAT ARE EXPOSED TO PRECIPITATION SHALL BE INSPECTED FOR EVIDENCE OF OR THE POTENTIAL FOR, POLLUTANTS ENTERING THE DRAINAGE SYSTEM.
  - THE INSPECTION DATE.
  - NAMES, TITLES AND QUALIFICATIONS OF PERSONNEL MAKING THE INSPECTION.
  - WEATHER INFORMATION FOR THE PERIOD SINCE THE LAST INSPECTION, INCLUDING A BEST ESTIMATE OF THE BEGINNING OF EACH STORM EVENT, DURATION OF EACH STORM EVENT AND APPROXIMATE AMOUNT OF RAINFALL FOR EACH STORM EVENT IN INCHES, AND WHETHER ANY DISCHARGES OCCURRED.
  - LOCATIONS OF:
    - DISCHARGES FROM SEDIMENT OR OTHER POLLUTANTS FROM THE SITE.
    - BMP'S THAT FAILED TO BE MAINTAINED.
    - BMP'S THAT FAILED TO OPERATE AS DESIGNED OR PROVED INADEQUATE FOR A PARTICULAR LOCATION.
    - WHERE ADDITIONAL BMP'S ARE NEEDED THAT DID NOT EXIST AT THE TIME OF THE INSPECTION.
    - CORRECTIVE ACTION REQUIRED INCLUDING ANY NECESSARY CHANGES TO THE SWP3 AND IMPLEMENTATION DATES.
- DISCHARGE LOCATIONS SHALL BE INSPECTED TO DETERMINE WHETHER EROSION AND SEDIMENT CONTROL MEASURES ARE EFFECTIVE IN PREVENTING SIGNIFICANT IMPACTS TO THE RECEIVING WATER RESOURCE OR WETLANDS.
- LOCATIONS WHERE VEHICLES ENTER OR EXIT THE SITE SHALL BE INSPECTED FOR EVIDENCE OF OFF-SITE VEHICLE TRACKING.
- THE PERMIT APPLICANT SHALL MAINTAIN FOR 3 YEARS FOLLOWING FINAL STABILIZATION THE RESULTS OF THESE INSPECTIONS, THE NAMES AND QUALIFICATIONS OF THE PERSONNEL MAKING THE INSPECTIONS, THE DATES OF THE INSPECTIONS, MAJOR OBSERVATIONS RELATING TO THE IMPLEMENTATION OF THE SWP3, A CERTIFICATION AS TO WHETHER THE FACILITY IS IN COMPLIANCE WITH THE SWP3, AND INFORMATION ON ANY INCIDENTS OF NON-COMPLIANCE DETERMINED BY THESE INSPECTIONS.

**MAINTENANCE**

ALL CONTROL PRACTICES SHALL BE MAINTAINED AND REPAIRED AS NEEDED TO ENSURE CONTINUED PERFORMANCE OF THEIR INTENDED FUNCTION UNTIL FINAL STABILIZATION. ALL SEDIMENT CONTROL PRACTICES MUST BE MAINTAINED IN A FUNCTIONAL CONDITION UNTIL ALL UP SLOPE AREAS THEY CONTROL REACH FINAL STABILIZATION. THE CONTRACTOR SHALL COMPLY WITH THE MAINTENANCE SCHEDULE CONTAINED IN THE APPROVED PLANS FOR THE PROPOSED EROSION CONTROLS. A WRITTEN DOCUMENT CONTAINING THE SIGNATURES OF ALL CONTRACTORS AND SUB-CONTRACTORS INVOLVED IN THE IMPLEMENTATION OF THE BMP'S SHALL BE MAINTAINED AT THE JOB SITE AS PROOF ACKNOWLEDGING THAT THEY HAVE REVIEWED AND UNDERSTAND THE CONDITIONS AND RESPONSIBILITIES OF THE SWP3.

WHEN INSPECTIONS REVEAL THE NEED FOR REPAIR, REPLACEMENT, OR INSTALLATION OF EROSION AND SEDIMENT CONTROL BMP'S, THE FOLLOWING PROCEDURES SHALL BE FOLLOWED:

- WHEN PRACTICES REQUIRE REPAIR OR MAINTENANCE: CONTROL PRACTICES IN NEED OF REPAIR OR MAINTENANCE, WITH THE EXCEPTION OF A SEDIMENT SETTLING POND, MUST BE REPAIRED OR MAINTAINED WITHIN 3 DAYS OF THE INSPECTION. SEDIMENT SETTLING PONDS MUST BE REPAIRED OR MAINTAINED WITHIN 10 DAYS OF THE INSPECTION.
- WHEN PRACTICES FAIL TO PROVIDE THEIR INTENDED FUNCTION: CONTROL PRACTICES THAT FAIL TO PERFORM THEIR INTENDED FUNCTION AS DETAILED IN THE SWP3 SHALL BE REPLACED WITH ANOTHER MORE APPROPRIATE CONTROL WITHIN 10 DAYS. THE SWP3 SHALL BE AMENDED TO SHOW THE NEW CONTROL PRACTICE.
- WHEN PRACTICES ON THE SWP3 ARE NOT INSTALLED: CONTROL PRACTICES REQUIRED BY THE SWP3 BUT NOT IMPLEMENTED AT THE TIME OF THE INSPECTION SHALL BE INSTALLED WITHIN 10 DAYS OF THE INSPECTION. IF THE PLANNED CONTROL IS NOT NEEDED, AN EXPLANATION AS TO WHY THE CONTROL IS NOT NEEDED SHALL BE ADDED TO THE SWP3.

**WASTE DISPOSAL**

A COVERED DUMPSTER SHALL BE MADE AVAILABLE FOR THE PROPER DISPOSAL OF GARBAGE, PLASTER, DRYWALL, GROUT, GYPSUM, AND OTHER WASTE MATERIALS. ALL CONTAINERS MUST BE LEAK PROOF. ALL WASTE MATERIAL INCLUDING TOXIC OR HAZARDOUS WASTE SHALL BE DISPOSED OF AT FACILITIES APPROVED FOR THE PERTINENT MATERIAL.

**CLEAN HARD FILL**

BRICKS, HARDENING CONCRETE, AND SOIL WASTE SHALL BE FREE FROM CONTAMINATION WHICH MAY LEACH CONSTITUENTS TO WATER RESOURCES OR WETLANDS. CLEAN CONSTRUCTION WASTES THAT WILL BE DISPOSED OF INTO THE PROPERTY SHALL BE SUBJECT TO ANY LOCAL PROHIBITIONS FROM THIS TYPE OF DISPOSAL.

**CONSTRUCTION AND DEMOLITION DEBRIS (C&DD)**

ALL C&DD SHALL BE DISPOSED OF IN AN OHIO EPA APPROVED C&DD LANDFILL AS REQUIRED BY OHIO REVISED CODE (ORC) 3714. MATERIALS WHICH CONTAIN ASBESTOS MUST COMPLY WITH AIR POLLUTION REGULATIONS (SEE OHIO ADMINISTRATIVE CODE (OAC) 3745-20).

**CONSTRUCTION CHEMICAL COMPOUNDS**

AREAS SHALL BE DESIGNATED FOR THE MIXING OR STORAGE OF COMPOUNDS SUCH AS FERTILIZERS, LIME, ASPHALT, OR CONCRETE. THESE DESIGNATED AREAS SHALL BE LOCATED AWAY FROM WATERCOURSES, DRAINAGE DITCHES, FIELD DRAINS, OR OTHER STORM WATER DRAINAGE AREAS.

**EQUIPMENT FUELING AND MAINTENANCE**

ALL FUEL/LIQUID TANKS AND DRUMS SHALL BE STORED IN A MARKED STORAGE AREA. SECONDARY CONTAINMENT SHALL BE PROVIDED FOR ALL FUEL OIL STORAGE TANKS. VEHICLE FUELING AND MAINTENANCE SHALL OCCUR IN DESIGNATED AREAS. THESE DESIGNATED AREAS SHALL BE LOCATED AWAY FROM WATERCOURSES, DRAINAGE DITCHES, FIELD DRAINS, OR OTHER STORM WATER DRAINAGE AREAS.

**SPILL PREVENTION CONTROL AND COUNTERMEASURES**

A SPILL PREVENTION CONTROL AND COUNTERMEASURES (SPCC) PLAN MUST BE DEVELOPED FOR SITES WITH ONE ABOVE GROUND STORAGE TANK OF 660 GALLONS OR MORE, TOTAL ABOVE GROUND TANK STORAGE OF 1330 GALLONS, OR BELOW GROUND STORAGE OF 42,000 GALLONS OF FUEL.

**CONCRETE WASH WATERS**

CONCRETE CHUTE OR OTHER CONCRETE WASH WATERS SHALL BE DISCHARGED INTO DESIGNATED AREAS ONLY. DESIGNATED AREAS SHALL BE IDENTIFIED WITH SIGNAGE AND LOCATED AWAY FROM WATERCOURSES, DRAINAGE DITCHES, FIELD DRAINS, OR OTHER STORM WATER DRAINAGE AREAS.

**CONTAMINATED SOILS**

ALL CONTAMINATED SOILS MUST BE TREATED AND/OR DISPOSED IN OHIO EPA APPROVED SOLID WASTE MANAGEMENT FACILITIES OR HAZARDOUS WASTE TREATMENT, STORAGE OR DISPOSAL FACILITIES (TSDFs). RUNOFF FROM CONTAMINATED SOILS SHALL NOT BE DISCHARGED FROM THE SITE. PROPER PERMITS SHALL BE OBTAINED FOR DEVELOPMENT PROJECTS ON SOLID WASTE LANDFILL SITES OR REDEVELOPMENT SITES.

**SPILL REPORTING REQUIREMENTS**

IN THE EVENT OF A SMALL RELEASE (LESS THAN 25 GALLONS) OF PETROLEUM WASTE, THE MENTOR FIRE DEPARTMENT SHALL BE CONTACTED AT (440) 255-1212.

IN THE EVENT OF A LARGER RELEASE (25 OR MORE GALLONS) OF PETROLEUM WASTE, CONTACT OHIO EPA AT 1-800-282-9378, THE MENTOR FIRE DEPARTMENT AT (440) 255-1212, AND THE LAKE COUNTY EMERGENCY MANAGEMENT AGENCY AT (440) 350-5499.

**OPEN BURNING**

OPEN BURNING IS NOT PERMITTED.

**DUST CONTROLS AND SUPPRESSANTS**

USED OIL SHALL NOT BE USED AS A DUST SUPPRESSANT. DUST CONTROLS MAY INCLUDE THE USE OF WATER TRUCKS TO WET DISTURBED AREAS, TARPING STOCKPILES, TEMPORARY STABILIZATION OF DISTURBED AREAS, AND REGULATION OF THE SPEED OF VEHICLES ON THE SITE.

**STREAM CROSSINGS**

STREAM CROSSINGS SHALL BE CONSTRUCTED ENTIRELY OF STONE, ROCK, OR CLEAN RECYCLED CONCRETE. SOIL OR EARTHEN MATERIAL MAY NOT BE USED. A 20 FOOT STONE APRON ON EITHER SIDE OF THE STREAM SHALL BE CONSTRUCTED TO PREVENT LOCALIZED SEDIMENTATION. THE CHANNEL BED AND BANKS SHALL BE RESTORED, AND ALL DISTURBED AREAS OF THE BANK WITHIN 50 FEET OF THE STREAM SHALL BE STABILIZED WITH SEED AND STRAW MULCH WITHIN 2 DAYS OF THE DISTURBANCE.

**PERMITS**

THIS SITE IS COVERED UNDER OHIO EPA GENERAL CONSTRUCTION PERMIT # \_\_\_\_\_.

THIS SITE IS COVERED UNDER OEP/A ARMY 401/ ARMY 404 PERMIT # \_\_\_\_\_.

**STRUCTURAL BMP'S**

PERMANENT BMP'S FOR POST CONSTRUCTION TREATMENT OF STORM WATER (CONVERSION OF SEDIMENT LAND TO STORM WATER POND) SHALL NOT BE INSTALLED UNTIL 70% OF THE DISTURBED AREA IS STABILIZED.

**SEEDING AND MULCHING**

SEDIMENT CONTROL SHALL BE ACCOMPLISHED BY SEEDING AND MULCHING UPON COMPLETION OF EXCAVATION OR FILL AND FINISHED GRADING IN ACCORDANCE WITH THE REQUIREMENTS OF O.D.O.T. ITEM 659 OR AS DIRECTED BY THE ENGINEER. THE FOLLOWING MIXTURES SHALL BE USED FOR SEEDING:

GENERAL USE (ODOT 659.09, CLASS 1)			
SEED MIX	SEEDING RATE	FERTILIZER	MULCH
KENTUCKY BLUEGRASS	3 LBS./1000 SQ FT	10-20-10 @ 20 LBS./1000 SQ FT	STRAW - 2 TONS/ACRE
CREEPING RED FESCUE	3 LBS./1000 SQ FT		
ANNUAL RYEGRASS	2 LBS./1000 SQ FT		
PERENNIAL RYEGRASS	2 LBS./1000 SQ FT		

ROADSIDE DITCHES AND SWALES (ODOT 659.09, CLASS 2)			
SEED MIX	SEEDING RATE	FERTILIZER	MULCH
PERENNIAL RYEGRASS	1.5 LBS./1000 SQ FT	10-20-10 @ 20 LBS./1000 SQ FT	STRAW - 2 TONS/ACRE
KENTUCKY 31 FESCUE	2.0 LBS./1000 SQ FT		
KENTUCKY BLUEGRASS	1.5 LBS./1000 SQ FT		

STEEP BANKS, CUT SLOPES, DETENTION AREAS, WHERE SLOPES ARE STEEPER THAN 3:1 (ODOT 659.09, CLASS 3C)			
SEED MIX	SEEDING RATE	FERTILIZER	MULCH
CROWN VETCH	0.9 LBS./1000 SQ FT	10-20-10 @ 20 LBS./1000 SQ FT	STRAW - 2 TONS/ACRE
PERENNIAL RYEGRASS	1.8 LBS./1000 SQ FT		
ANNUAL RYEGRASS	0.3 LBS./1000 SQ FT		

TEMPORARY EROSION CONTROL (ODOT 659.09, CLASS 7)			
SEED MIX	SEEDING RATE	FERTILIZER	MULCH
ANNUAL RYEGRASS	2.02 LBS./1000 SQ FT	10-20-10 @ 20LBS./1000 SQ FT	STRAW - 2 TONS/ACRE

REV. NO.	DESCRIPTION	DATE	BY	CHKD.
1.				
2.				
3.				
4.				

DATE: <u>      JULY, 2014      </u>
DRAWN BY: <u>      BA      </u>
CHECKED BY: <u>      BA      </u>
APPROVED BY: <u>      DAS      </u>